

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-21,605-0000

LEASE NAME Hays Trust J

WELL NUMBER 1

560 Ft. from S Section Line

4720 Ft. from E Section Line

SEC. 4 TWP. 34 RGE. 31 (E or W)

COUNTY Seward

Date Well Completed 05-13-97

(Abandoned)

Plugging Commenced 05-20-97

Plugging Completed 05-21-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company, Inc.

ADDRESS 110 N. Market, Suite 205 Wichita, KS 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well D&A (attempted completion)

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-20-97 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Miss. Chester Depth to Top 5662 Bottom 5969 T.D. 6020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Conductor Casing	0	162'	13 3/8"	162'	None
	Surface Casing		1376	8 5/8"	1376'	None
	Production Casing		5943	4 1/2"	5943'	2624

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP was at 5600 - fluid level 5300. Mixed 10 sx plug from 5300 to 5200 and displaced w/ mud. Recovered 2624 and pulled to 1428. Mixed 50 sx plug 1428 to 1278. Pull 4 1/2 to 570. Mixed 40 sx plug 570 to 470. Pull to 40. Mixed 10 sx plug 40 to 0. Cut off to cap 8 5/8 4 ft. below G.L.  
Gary Winters - KCC Rep.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Pickrell Drilling Company, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) C.W. Sebitts, President  
110 N. Market, Suite 205 Wichita, KS

Subscribed and sworn to before me this 5th day of June, 19 97

Karen A. Mans McGee  
Karen A. Mans McGee Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1997  
CONSERVATION DIVISION  
Wichita, Kansas





BAKER SERVICE TOOLS - TALLY PAD

15-175-21605-0000

New Completion  Workover

Oil Company \_\_\_\_\_ Well No. 1 Field Arkalon Lease Hays Trust J  
 Company Man \_\_\_\_\_ Date Drilled Apr. 1997 County Seward State Kansas

SW SW Sec 4-34S-31W  
 15-175-21605

162' Base 13 3/8" Conductor w/185 Sx 60/40 Poz 29 gel (Circ.)

1378' Base 8 5/8" 24.0# w/500 Sx ALW plus 150 Sx Class A (Circ.)

RECEIVED  
 KANSAS CORPORATION COMMISSION

MAY 19 1997

CONSERVATION DIVISION  
 WICHITA, KS

Herrington	2444
Krider	2471
Winfield	2506
Council Grove	2847
Cottonwood	3007
Heebuer	4155
Miss Chester Perf's housing	4294
Marin	4998
Morrow	5527
Miss Chest.	5659

4863 T.O.C.

- 5663-5666
- 5710-5716
- 5766-5774
- 5811-5814
- 5848-5850

Miss Chester Perf's housing

5907 PSTD (Loggers)

5943' Base 4 1/2" 10.5# Csg. w/135 Sx 60/40 Poz plus 100 Sx Com.

6020' RTD

REMARKS:

Propose to plug by —

- a) Set CIBP at approx 5600'
- b) Use dump bailer to spot 4 Sx. of cement on B.P.
- c) Cut and recover casing.
- d) As foot w/ casing spot cement plugs
  - 1) 50 Sx at 1408
  - 2) 40 Sx at 700
  - 3) Cement 40 ft. to surface.