

RECEIVED  
STATE CORPORATION COMMISSION

JUL 25 1974

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

CONSERVATION DIVISION  
Wichita, Kansas Seward

County, Sec. 4 Twp. 34S Rge. 31 (E) (W) X

Location as "NE/CNW/SE/SW" or footage from lines 1275' F S & W Lines

Lease Owner Patrick and Vaughn

Lease Name Hays "A" Well No. 1

Office Address 708 First Nat. Center Oklahoma City, Okla. 73102

Character of Well (completed as Oil, Gas or Dry Hole) Gas well

Date well completed 12/23/64 1964

Application for plugging filed 1964

Application for plugging approved 1964

Plugging commenced 4-9 1974

Plugging completed 4-11 1974

Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production March 1974

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves

Producing formation Morrow Sand Depth to top 5644 Bottom 5652 Total Depth of Well 6000 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow sand	Gas	5644	5652	8 5/8	1455	none
				4 1/2	5770	3030

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pump 20 sks. of cement to 5515  
Pump 35 sks. of cement @ 900 to 800  
Put 15 sks. of cement @ 45 to 0

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511  
Address Box 506 Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Oklahoma ss.  
Jack H. Vaughn (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Suite A- 5813 N. Grand Blvd., Okla. City  
Oklahoma 73118 (Address)

Subscribed and sworn to before me this 24th day of July 1974

My Commission Expires June 10, 1977  
[Signature] Notary Public.

15-175-30080-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ANADARKO PRODUCTION  
Farm- Hays " A " No. 1

SEC. 4 T. 34 R. 31W  
Approx C SW  
1275' N of SL & 1275' E of WL

Total Depth. 6000'  
Comm. 10-15-64 Comp. 12-23-64  
Shot or Treated. 5645-49 16 shots 500 gal acid  
Contractor. Earl Wakefield  
Issued. 3-27-65

County Seward  
KANSAS



Elevation. 2548.37' GL

Production. 2130 MCFG

CASING:

8 5/8" 1454' cem w/ 775 sx  
4 1/2" 5770' cem w/ 215 sx

Figures Indicate Bottom of Formations.

sand	380
sand & red bed	990
red bed	1455
anhydrite & shale	1876
shale	2406
shale & lime	3200
lime	3739
shale & lime	4718
lime	5341
shale & lime	5898
lime	6000
Total Depth	

TOPS: SCOUT

Krider	2480
Lansing	4308
Marmaton	5000
Morrow	5524
Lower Morrow sand	5642-51
Mississippi	5651
St. Genevieve	5956

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 28 1974  
CONSERVATION DIVISION  
Wichita, Kansas