

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,931-0000

LEASE NAME CITY OF LIBERAL

WELL NUMBER #1-27

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2110' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 27 TWP. 34 RGE. 33 (X) or (W)

COUNTY Seward

LEASE OPERATOR DONALD C. SLAWSON

ADDRESS 20 North Broadway, Suite 700, Oklahoma City, OK 73102

PHONE#(405) 232-0201 OPERATORS LICENSE NO. 5181

Date Well Completed 1/08/87

Character of Well Dry

Plugging Commenced 1/07/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1/08/87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Liberal (State Plugger-Dick Capp)

Is ACO-1 filed? Attached If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 6,500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1,575'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

At the time of plugging operations the hole was full of 9.2+ ppg drilling mud. Cement plugs were placed as follows: 100 sx Class 'H' from 3,339' to 3,100'; 50 sx Class 'H' from 1,625' to 1,525'; 25 sx Class 'H' from 660' to 600'; and 20 sx Class 'H' from 0' to 60'. 15 sx Class 'H' in rathole. Casing cut off 3' below GL & welded on Plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor The Western Company License No. #528

Address P.O. Box 850570, Yukon, Oklahoma, 73085

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Daniel G. Wilson, Division Engineer

(Employee of Operator) XXXXXXXXXXXXXXX of

above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 20 North Broadway, Suite 700

SUBSCRIBED AND SWORN TO before me this 14th day of April, 19 87

[Signature]
RECEIVED Public
STATE CORPORATION COMMISSION

My Commission Expires: 1/31/91

APR 17 1987

Form CP-4
Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas

15-175-20931-0000

Debbie
pls file

State of Kansas



RECEIVED

APR 13 1987

OKD

Mike Hayden
Michael Lennen
Margalee Wright
Keith R. Henley
Judith A. McConnell
Brian J. Moline

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286
Ph. 316-263-3238

April 10, 1987

City of Liberal # 1-27
Sec. 27-34S-33W
Seward County

Donald C. Slawson
20 North Broadway, Suite 700
Oklahoma City, Okla. 73102

RE: CP-4 (Well Plugging Record)

Dear Sir:

The above-described plugging form has not been received by the Conservation Division. K.A.R. 82-3-117 requires such form to be filed within 30 days after the plugging of the well.

You have been notified by the Conservation Division staff regarding the filing of this form. Because you have ignored your responsibilities regarding this matter, it has been turned over to the Legal Department. If I don't receive this form from you within 10 days from the date of this letter, you will be subject to a \$100 penalty and possible license suspension until the required form is received.

If you have any questions, please feel free to contact the Plugging Department at (316) 263-3238.

Sincerely,

Shari M. Feist

Shari M. Feist
Assistant General Counsel

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1987

CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date Dec 21 1986
month day year 3:27

OPERATOR: License # 5181
Name SLAWSON, DONALD C.
Address 20 North Broadway, Suite 700
City/State/Zip Oklahoma City, OK 73102
Contact Person Daniel G. Wilson
Phone (405) 232-0201

CONTRACTOR: License # 5657
Name Slawson Drilling Company
City/State Great Bend, Kansas

Well Drilled For: Well Class: Type Equipment:
☒ Oil ☐ SWD ☐ Infield ☒ Mud Rotary
☒ Gas ☐ Inj ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

_____ cementing will be done immediately upon setting production casing.

Date 12/19/86 Signature of Operator or Agent James C. Ramsberg Title Operations Manager

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 1
This Authorization Expires 6-19-87 Approved By 12-19-86

Spud 12-22-86
Set 1570 +

API Number 15-175-20,931-0000
E/2 NE..SE... Sec. 27.. Twp. 34.. S, Rg. 33.... ☒ East
2110 Ft. from South Line of Section
330. Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County Seward
Lease Name City of Liberal Well #1-27
Ground surface elevation 2823 feet MSL
Domestic well within 330 feet: ☐ yes ☒ no
Municipal well within one mile: ☐ yes ☒ no
Surface pipe by Alternate: 1 ☒ 2 ☐
Depth to bottom of fresh water 180'
Depth to bottom of usable water 400' 550'
Surface pipe planned to be set 1570'
Projected Total Depth 6500 feet
Formation Chester

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 5800-5900 feet depth with 75 sxs of Class 'H'
2nd plug @ 300-1620-1520 feet depth with 50 sxs of Class 'H'
3rd plug @ 3-33 feet depth with 75 sxs of Class 'H'
4th plug @ 660 feet depth with 25 sxs of
5th plug @ 40-0 feet depth with 10 sxs of
(2) Rathole with 13 sxs (b) Mousehole with 10 sxs

PUSHER Jack - Richardson
TD 6500 FORMATION
SURFACE PIPE 8 5/8 @ 1575
ANHYDRITE ELEVATION 2823
STARTING TIME & DATE 7:30 AM 12-22-86
COMPLETION TIME & DATE 2:30 PM 12-22-86
1st PLUG @ 3339 FT. W/ 100 SX
2nd PLUG @ 1603 FT. W/ 50 SX
3rd PLUG @ 660 FT. W/ 25 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ 40-0 FT. W/ 10 SX
CEMENT COMPANY Western
TECHNICIAN

STATE CORPORATION COMMISSION

JAN 12 1987

CONSERVATION DIVISION
Wichita, Kansas