

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,792-0000

LEASE NAME James

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-19

3300' Ft. from S Section Line

660' Ft. from E Section Line

LEASE OPERATOR J M A Resources

SEC. 19 TWP. 34S RGE. 34W (E) or (W)

ADDRESS P.O.Box 976 Liberal, Kansas 67905-0976

COUNTY Seward

PHONE# (316) 624-8388 OPERATORS LICENSE NO. _____

Date Well Completed _____

Character of Well D & A

Plugging Commenced 3-11-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-14-94

The plugging proposal was approved on 3-9-94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? N/A

Producing Formation MORROW Depth to Top 5836-40 Bottom T.D. 6750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>MORROW</u>	<u>WATER</u>	<u>5836</u>	<u>40</u>	<u>8 5/8</u>	<u>1686</u>	<u>0</u>
				<u>5 1/2</u>	<u>6684</u>	<u>2525</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pump 20 sks. of cement & 1 sk. of hulls to 5700'
Pump 35 sks. of cement from 2500' to 2400' Pump 50 sks. of cement from 1720'
to 1620' Pump 40 sks. of cement from 700 to 600' Put 10 sks. of cement from
40 to 0 Cut off & cap 8 5/8 10' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O.Box 506 Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J M A Resources

STATE OF Kansas COUNTY OF Seward, ss.


(Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Harold K. ...

(Address) Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 94

Denise Robinson



Notary Public

My Commission Expires _____

RECEIVED
STATE CORPORATION COMMISSION
APR 01 1994
CONSERVATION DIVISION
Wichita, Kansas