

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2125
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 119-20,964 0000

LEASE NAME Wynona A Trust

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

380 Ft. from S Section Line

380 Ft. from E Section Line

LEASE OPERATOR Eagle Creek Corporation

SEC. 8 TWP. 34 RGE. 29 (S or W)

ADDRESS 107 N. Market #411 Wichita KS 67202

COUNTY Meade

PHONE# (316) 264 8044 OPERATORS LICENSE NO. 30129

Date Well Completed _____

Character of Well _____

Plugging Commenced 8-21-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-25-98

The plugging proposal was approved on 8-20-98 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation Swope Depth to Top 5048 Bottom 5041 T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 3/8</u>	<u>1587</u>	<u>—</u>
				<u>4 1/2</u>	<u>5433</u>	<u>2617</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.
Mixed 2 5x hulls + 20 5x cmt to plug perfs from 5048 to 4848. Recovered 2617 ft. 4 1/2. Pulled to 1620 + mixed 50 5x plug from 1620 to 1470. Pulled to 660 + mixed 25 5x plug from 660 to 560. Pulled to 40 + mixed 10 5x plug from 40 to 0. Cut off + capped 8 3/8 4 ft. below ground level.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EAGLE CREEK CORPORATION

STATE OF KANSAS COUNTY OF SEDBWICK, ss.

DAVID L. CALLEWAERT (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) David L. Callewaert

(Address) 107 N. MARKET #509 Wichita

9-17-98
SUBSCRIBED AND SWORN TO before me this 16th day of SEPT., 19 98

My Commission Expires: 6-12-99

NOTARY PUBLIC - State of Kansas
VICCI L. LORTZ
My Appt. Exp. _____