

15419-0061-0000 Comm

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Meade County, Sec. 8 Twp. 34 Rge. 29 ~~26~~ (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Cen. SW/4 NE/4

Lease Owner J.M. Huber Corp.

Lease Name H.G. Adams "A" Well No. 1

Office Address Box 978, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-26-53 19

Application for plugging filed 10-26-53 19

Application for plugging approved 10-26-53 19

Plugging commenced 10-31-53 19

Plugging completed 11-2-53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

		1980'	
	X	1980'	

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well M.A. Rives

Producing formation Depth to top Bottom Total Depth of Well 6110 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8"	640'	None
				9 5/8"	2500'	None
				5 1/2"	5937'	2757'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Shot off and recovered 2757' of 5 1/2" casing. Plugged back with Crushed rock from total depth to 5820'. Dumped 5 sacks cement at 5820' with dump bailer. Top of cement 5790'. Filled hole with mud from 5790' to 2500'. Set a rock bridge and 20 sacks of cement at 2500'. Top of cement 2460'. Filled hole with mud to 550'. Set rock bridge and 20 sacks cement at 550'. Top of cement 490'. Filled with mud to 20'. Set a rock bridge at 20'. Filled with 15 sacks cement to top of hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1953 11-13-53

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.

Address Box 711 Great Bend, Kansas

STATE OF KANSAS COUNTY OF Seward, ss.

R.E. McDaniel (employee of owner) or (owner/proprietor) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.E. McDaniel

Box 978 Liberal, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10 day of November, 1953

J. K. Tyler Notary Public.

My commission expires 7-27-57

23-8390-s 6-51-20M

PLUGGING
FILE SEC 8 T 34 R 29W
BOOK PAGE 138 LINE 39

WELL LOG

Well name: J.M. Huber # 1 H.G. Adams "A"
Well location: Cen. SW/4 NE/4 Sec 8, Twp 34S, Rge 29W
Meade Co., Kansas
Date commenced: 9-20-53
Date completed: 10-26-53
Total depth: 6110'
Character of well: Dry hole.

FORMATION

DEPTH

Surface sand and shells	0-560'
Red bed and shells	560-1460'
Red bed and shale	1460-1774'
Shale	1774-2135'
Lime and shale	2134-2501'
Sandy lime and shale	2501-2971'
Lime	2971-3790'
Lime and shale	3790-3940'
Shale	3940-4265'
Lime and shale	4265-4845'
Lime	4845-5615'
Lime and shale	5615-5760'
Shale and sand	5760-5873'
Lime and shale	5873-6007'
Lime	6007-6110'

5873

Total Depth 6110'

STATE OF KANSAS, COUNTY OF SEWARD, ss

R.E. McDaniel employee of owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

R.E. McDaniel

Subscribed and Sworn to before me this 10 day of Nov. 1953

J. L. ...
Notary Public

My commission expires 7-27-57

PLUGGING
FILE SEC 8 T 34 R 29W
BOOK PAGE 138 LINE 39

COMMISSIONER OF PUBLIC LANDS
Wichita, Kansas