

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Seward

County. Sec. 32 Twp. 34S Rge. 31W (E) (W)

NORTH


Locate well correctly on above  
Section Plat

Location as "NE/CNW%SW%" or footage from lines \_\_\_\_\_  
 Lease Owner J. M. Huber Corporation  
 Lease Name Risley Well No. 1  
 Office Address P. O. Box 978 - Liberal, Kans.  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 4-25-55 19\_\_\_\_  
 Application for plugging filed 4-26-55 19\_\_\_\_  
 Application for plugging approved 4-26-55 19\_\_\_\_  
 Plugging commenced 4-26-55 19\_\_\_\_  
 Plugging completed 4-27-55 19\_\_\_\_  
 Reason for abandonment of well or producing formation Dry Hole  
 If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 6200' Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1520'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole w/ mud laden fluid to 500'. Spotted 35 sacks of Pozmix through the drill pipe on top of Halliburton Plug.  
Filled hole w/ mud laden fluid to 35', spotted 15 sacks of Pozmix on top of Halliburton Plug.

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 30 1955 4-30-55  
 CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Own tools  
 Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
I, W. W. Henson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
 (Signature) W. W. Henson

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 19 55

My commission expires July 27, 1957

J. R. Key, Jr.  
 Notary Public.

**PLUGGING**  
 FILE SEC 22 T 34 R 31W  
 BOOK PAGE 115 LINE 7

Well Record

Well Name: Risley #1

Well Location: Center of SE/4 of the NW/4 of Section 32,  
Township 34S, Range 31 West, Seward County,  
Kansas.

Well Owner: J. M. Huber Corp.

Drilling Commenced: 4-3-55  
Drilling Completed: 4-25-55  
Well Completed: 4-26-55

Total Depth: 6200'

<u>Formation</u>	<u>Depth</u>
Sand, clay, gyp & shells	0-608
Redbed	608-670
Redbed & shells	670-1020
Redbed & shells & sand	1020-1207
Redbed & shells	1207-1520
Lime & redbed	1520-1720
Redbed & shale	1720-1848
Shale & shells	1848-1895
Redbed & shale	1895-2072
Lime & shale	2072-2640
Lime	2640-2740
Lime & shale	2740-3686
Lime	3686-3820
Lime & shale	3820-4623
Lime	4623-4678
Lime & chert	4678-4820
Lime & shale	4820-4964
Lime	4964-5223
Lime & shale	5223-5306
Lime	5306-5440
Lime & chert	5440-5490
Lime	5490-5564
Lime & chert	5564-5652
Lime	5652-5706
Lime & shale	5706-5900
Shale & ?	5900-5970
Lime & shale	5970-6020
Lime, shale & sand	6020-6092
Lime & shale	6092-6200
Total Depth	6200

RECEIVED  
COMMISSION

6-55

REGISTRATION DIVISION - Page 1 -  
Kansas

**PLUGGING**  
FILE SEC 32, 34, 31W  
BOOK PAGE 115 LINE 7

Well Record (Risley #1)  
Page 2.

STATE OF KANSAS, COUNTY OF SEWARD, SS:

W. W. Henson, employee of owner of the above named well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

W. W. Henson

Subscribed and sworn to before me this 29 day of April, 1955.

J. L. Taylor  
Notary Public

My commission expires:

7-27-57