

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-175-218870000

LEASE NAME Max

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-28

4775 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 28 TWP. 34 RGE. 31 (E or W)

COUNTY Seward

Date Well Completed 2-20-03

Plugging Commenced 3-20-03

Plugging Completed 3-21-03

LEASE OPERATOR Raydon Exploration, Inc.

ADDRESS 9400 N Broadway, Ste. 400 OKC OK

PHONE (620) 624 0156 OPERATORS LICENSE NO. 30604

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-20-03 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chase Depth to Top _____ Bottom _____ T.D. 6450'

Show depth and thickness of all water, oil and gas formations.

RECEIVED

APR 14 2003

KCC WICHITA

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 5/8</u>	<u>1665</u>	<u>-</u>
				<u>4 1/2</u>	<u>5283</u>	<u>2036</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character, of same and depth placed, from _____ feet to _____ feet each so
Mixed 200 lb. hulls & 20 sx cmt to plug perfs from 2612 to 2412. Shot & pull 4 1/2 to 1700. Circ. hole w/mud & mixed 50 sx 1700 to 1550
40 sx 600 to 480 10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raydon Exploration, Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill, agent for Raydon Exploration, Inc. (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Crown Consulting, Inc.

PO Box 1816, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 8th day of April, 2003

[Signature]
Notary Public

My Commission Expires:

NOTARY PUBLIC, State of Kansas
Seward County
HELEN M. SMITH
My Appt. Exp. 3-5-2005

Form CP-
Revised 05-01

PROPOSED METHOD OF PLUGGING (Cont):

lay down pipe, pump 10 sack plug from 40-4', cut off 8-5/8" 4' below ground level and cap with ID plate.