

15-175-21843-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1517521843
LEASE NAME FITZGERALD
WELL NUMBER C-1H

RECEIVED
JAN 10 2003
KCC WICHITA

NOTICE: TYPE OR PRINT
Fill out completely
and return to Cons. Div.
office within 30 days

3300 Ft. from S Section Line
4620 Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION
ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101
PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

SEC. 2 TWP. 34S RGE. 33 (X) or (W)
COUNTY SEWARD

Character of Well GAS

Date Well Completed 6-19-2001
Plugging Commenced 12-31-2002

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-1-2003

The plugging proposal was approved on 12-26-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2602 Bottom 2669 T.D. 5140

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2602	2669	8-5/8	1631	0
				5-1/2	5140	1910

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PUMP 4 SXS HULLS AND 25 SXS CMT FROM 2602 TO 2402. PULL FREE POINT AND SHOOT OFF 5-1/2 CSG AT 1910. PUMP 50 SXS CMT FROM 1660 TO 1510. PUMP 40 SXS CMT FROM 550 TO 430. SPOT 10 SXS CMT FROM 40 TO 3. CUT OFF AND CAP 8-5/8 CSG 3 BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151


Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER



(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 7 day of January, 2003
Lori Pearson
Notary Public

My Commission Expires: 2/26/05

OR