

15-175-00004-0008

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Seward County. Sec. 1 Twp. 34 Rge. (E) 33 (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner Musgrove Petroleum Corporation

Lease Name WEBB Well No. 1

Office Address 518 Petroleum Bldg., Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed MARCH 14, 19 55

Application for plugging filed verbally - April 15, 1955

Application for plugging approved verbally & written April 15, 1955

Plugging commenced April 21, 1955

Plugging completed April 21, 1955

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 6236' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	638'	
				8-5/8"	2718'	1302'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 500'.  
Set 1st plug w/ 15' rock bridge & 25 sx cement, at 500'.  
Filled hole with mud to 25'.  
Set 2nd plug w/10' rock bridge and 15 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Company  
Address Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
I, Gordon L. Koelling (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Gordon L. Koelling*  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1955

*Alma E. Lane*  
Notary Public.

My commission expires July 16, 1955.

RECEIVED 24-7368-8 3-53-20M  
STATE CORPORATION COMMISSION  
4-29-55  
APR 29 1955  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILED SEC 1 T 34 R 33 W  
BOOK PAGE 44 LINE 29

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	WEBB #1
LOCATION:	C SE NW, Section 1-34-33 Seward County, Kansas.
COMMENCED:	February 10, 1955
COMPLETED:	March 14, 1955

0	590	Sand & shells
590	641	Red shale
641	675	Shale
675	1585	Shale & lime
1585	2340	Lime
2340	2375	Anhydrite
2375	2668	Lime & anhydrite
2668	2840	Lime
2840	3130	Shale & lime
3130	3620	Lime
3620	3725	Lime & shale
3725	3805	Lime
3805	4115	Shale & lime
4115	4175	Lime
4175	4229	Shale
4229	4420	Lime
4420	4475	Lime & shale
4475	4571	Lime
4571	4669	Lime & shale
4669	5010	Lime
5010	5115	Lime & sand
5115	5465	Lime
5465	5681	Shale & lime
5681	5720	Lime
5720	5849	Lime & shale
5849	5880	Sand
5880	5912	Sandy lime & shale
5912	6236	Lime & shale
	6236	Rotary Total Depth

Set 13-3/8" surface at 638' with 500 sacks Posmix & 2% calcium chloride

Set 8-5/8" at 2718' w/220 sacks cement 1% calcium chloride

Dry and Abandoned.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the WEBB #1, C SE NW Section 1-34-33, Seward County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling  
 Secretary/Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 18th day of March, 1955.

Anna E. Rose  
 Notary Public

My commission expires July 16, 1955.

RECEIVED STATE OF KANSAS

PLUGGING  
 SUR SEC 1 34 33W  
 COR PAGE 111 LINE 29