

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-22567-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corporation KCC LICENSE # 5506 *6/99*
(owner/company name) (operator's)

ADDRESS 1966 SE Rodeo Drive Rd. P.O. Box 168 CITY Medicine Lodge

STATE Kansas ZIP CODE 67104 CONTACT PHONE # (316) 886-5606

LEASE Donovan WELL# #1 SEC. 10 T. 34 R. 13 (East/West)

SE - SW SPOT LOCATION/QQQQ COUNTY Barber

990 FEET (in exact footage) FROM (S/N) (circle one) LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE NONE SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 10 3/4" SET AT 220 CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4770' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4634' to 4638'

ELEVATION 1694' T.D. 5429' PBDT 4737 ANHYDRITE DEPTH 1400'
(G.L. K.E.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING CIBP @ 4650' and 2 sax cmt. Cut and lay down csg. From surface pump 300# hulls - 10 sax gel - 50 sax cmt - 10 sax gel - 100 # hulls - 8 5/8" wiper plug and 100 sax cmt.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# (316) 886-5606

ADDRESS 1966 SE Rodeo Drive Rd. P.O. Box 168 City/State Medicine Lodge, Ks. 67104

PLUGGING CONTRACTOR Clarke Corporation KCC LICENSE # 5105 422270 *6/99*
(company name) (contractor's)

ADDRESS Medicine Lodge, Ks. 67104 PHONE # (316) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 11/15/98

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 10/21/98 AUTHORIZED OPERATOR/AGENT: Carl W. Durr
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

October 27, 1998

Woolsey Petroleum Corporation
1966 SE Rodeo Drive Rd., PO Box 168
Medicine Lodge, Ks. 67104

Donovan #1
API 15-00722567
NE SE SW
Sec. 10-34S-13W
Barber County

Dear Carl W. Durr,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888