

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-007-22,109-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR American Energies Corporation OPERATORS LICENSE NO. 5399

ADDRESS 575 Fourth Financial Center, Wichita, Kansas 67202 PHONE # ( ) 316-263-5785

LEASE (FARM) Donovan "A" WELL NO. 1 WELL LOCATION E/2 COUNTY Barber

SEC. 10 TWP. 34 RGE. 13 (X) or (W) TOTAL DEPTH 4828 PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A XX SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 523' CEMENTED WITH 275 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug well with 135 sxs 60/40 poz, 6% gel as follows: 50 sxs-1275'; 50 sxs-550'; 10 sxs-40' with solid bridge; 10 sxs-mousehole; 15 sxs-rathole.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN \_\_\_\_\_ at once

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Norman Hogan (Toolpusher-Rig 2) PHONE # ( ) 316-672-7514

ADDRESS P. O. Box 329, Pratt, Kansas 67124

PLUGGING CONTRACTOR Wheatstate Oilfield Services, Inc. LICENSE NO. 5149

ADDRESS P. O. Box 329, Pratt, Kansas 67124 PHONE # ( ) 316-672-7514

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Tracy C. Shaver  
STATE CORPORATION COMMISSION (Operator or Agent)

RECEIVED  
1-17-86  
JAN 17 1986

DATE: 1/14/86

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 12 14 85  
month day year

API Number 15- 007-22,109-0000

OPERATOR: License # 5399  
Name American Energies Corporation  
Address 575 Fourth Financial Center  
City/State/Zip Wichita, Kansas 67202  
Contact Person Martha Albright  
Phone 316/263-5785

C W/2 NE Sec 10 Twp 34 S, Rge 13  East  
(location)  West

3960 Ft North from Southeast Corner of Section  
1980 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5149  
Name Wheatstate Oilfield Services, Inc.  
City/State Pratt, Kansas

Nearest lease or unit boundary line 660 feet.  
County Barber  
Lease Name DONOVAN "A" Well# 1  
Domestic well within 330 feet: yes  no  
Municipal well within one mile: yes  no

Well Drilled For: Well Class: Type Equipment:  
Oil Swd Infield  Mud Rotary  
 Gas Inj Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 100 feet  
Lowest usable water formation  
Depth to Bottom of usable water 400-200 feet  
Surface pipe by Alternate: 1  2  
Surface pipe to be set 500 feet  
Conductor pipe if any required N/A feet  
Ground surface elevation feet MSI  
This Authorization Expires 6-11-86  
Approved By 12-11-85 R. [Signature]

If OWWO: old well info as follows:  
Operator N/A  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 5000' feet  
Projected Formation at TD Mississippian  
Expected Producing Formations Miss, Elgin

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 12/9/85 Signature of Operator or Agent [Signature] Title Vice-President Form C-1 A/84

8 5/8" 500 speed 12-19-85

PUSHER	M. Hogan	FORMATION	MISS
TD	4850	SURFACE PIPE	8 5/8" @ 522'
ANEHYDRITE	2068'	ELEVATION	N/A
STARTING TIME & DATE	12-1-86		
COMPLETION TIME & DATE	12:30 pm		
1st PLUG @	2075'	FT. W/	50 SX
2nd PLUG @	550'	FT. W/	50 SX
3rd PLUG @	40'	FT. W/	70 SX
4th PLUG @		FT. W/	SX
RAT HOLE CIRCULATED W/			15 SX
MOUSE HOLE CIRCULATED W/			10 SX
WATER WELL PLUGGED W/			SX
CEMENT COMPANY	BT-Titan		
TECHNICIAN	60140 67%		

JAN 6 1986



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

**Oilfield Services, Inc.**

DRILLER'S WELL LOG

Donovan "A" #1  
 C W/2 NE Sec. 10-34S-13W  
 Barber County, Kansas  
 Commenced: 12-19-85  
 Completed: 1-1-86  
 API #15-007-22,109  
 Operator: American Energies Corporation


Depth		Formation	Remarks
From	To		
0	1035	Red Bed	Ran 12 joints (510') new, 23#, 8 5/8" surface casing. Set at 522' with 125 sxs lite, 3% cc and 150 sxs Class A, 3% cc, 2% gel. Plug down at 7 a.m. Cement did circulate. Job by B.J. Titan, Medicine Lodge, Kansas.  RTD 4950'  Plugged well with 135 sxs 60/40 poz, 6% gel as follows: 50 sxs-1275'; 50 sxs-550'; 10 sxs-40' with solid bridge; 10 sxs in mousehole; 15 sxs in rathole. Plug down at 12:30 p.m. on 1-1-86. Job by B.J. Titan, Medicine Lodge. State plugger was out of Dodge City, Kansas office.
1035	1665	Red Bed, Shale	
1665	1940	Shale	
1940	2165	Lime, Shale	
2165	3205	Shale	
3205	4950	Lime, Shale T.D.	

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Tracy C. Graven*  
 TRACY C. GRAVEN, CONTROLLER



*Mary L. Tjaden*  
 NOTARY PUBLIC

My Commission Expires:

3/22/88

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 17 1986

CONSERVATION DIVISION  
 WASHINGTON, KANSAS