

RECEIVED

AUG 20 2002

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 119-210670000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Raydon Exploration, Inc. KCC LICENSE # 30604

ADDRESS 9400 N. Broadway, Ste. 400 (owner/company name) CITY Oklahoma City (operator's)

STATE OK ZIP CODE 73114 CONTACT PHONE # (620) 624-0156

LEASE Irish Flats WELL# 1-4 SEC. 04 T. 34S R. 29 (East/West)

SE - NW SPOT LOCATION/OOOO COUNTY Meade

1980 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE 20 SET AT 50' CEMENTED WITH 6 yards 6 sk SACKS <sup>grout</sup>

SURFACE CASING SIZE 8-5/8" SET AT 1616' CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 6349' CEMENTED WITH 170 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 6265-6274', CIBP at 6200', 5884-5390'

ELEVATION 2543/2554 T.D. 6350 PBD 6200' ANHYDRITE DEPTH 5842-5848'  
(G.L./K.B.) (Stone Corral Formation)

Note: packer and tubing sanded in after frac job  
CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Free point tubing and cut off, set CIBP above

stub, 2 sacks cement on plug, 50 sack plug at 1650', 80 sack plug at

800', 20 sack plug at 40', 60/40 cement with 6% gel, 15 sacks gel on side.

(If additional space is needed attach separate page)  
Per Mike Maier with KCC/Dodge City.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Keith Hillman PHONE# (620) 624-0156

ADDRESS Crown Consulting, Inc. City/State Liberal, KS 67905-1816

PLUGGING CONTRACTOR Sargent & Lillard Casing Pullers SKCC LICENSE # 32833

ADDRESS PO Box 1450, Woodward, OK PHONE # 680-256-2728

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) as soon as possible

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 08-19-02 AUTHORIZED OPERATOR/AGENT: \_\_\_\_\_  
(signature)



## Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Raydon Exploration, Inc.  
9400 N. Broadway #400  
Oklahoma City, OK 73114

August 21, 2002

Re: IRISH FLATS #1-4  
API 15-119-21067-00-00  
SENW 4-34S-29W, 1980 FNL 1980 FWL  
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely  
Handwritten signature of David P. Williams in cursive.

David P. Williams  
Production Supervisor