

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21957-00-01 Spot: SWSW
Sec: 17 Twnshp & Dir: 34 S Rng & Dir: 2 W
Feet: 750 frm N/S: S Feet: 4750 frm E/W: E
Lease/Unit Name: MARY Well Number: 1
County: SUMNER Total Vertical Depth: 4730 feet

Operator License No.: 4941

Conductor Pipe: Size

feet:

Operator Name: Union Valley Petroleum CorporSurface Casing: Size 8.625feet: 263Address: RR 4, Box 120 YProduction: Size 5.5feet: 4730Enid, OK 73701

8/16

153.73

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 06/22/2000 1:00 PMPlug Co. License No.: 8733Plug Co. Name: Dunkin, Jerry, Inc.Proposal Received from: Paul YoungbloodCompany Name: Union Valley Petro. Inc.OpRepPhoneNo: (580) 237-3959

Proposed Plugging Method: Perfs 4140-56, 4300-48, 4422-4455. Set CIBP 50' above perfs, Shoot casing and pull to 700, spot 35sxs of cement. Pull casing to 310' and circulate cement to surface. Pull pipe and top off cement.

Plugging Proposal Received By: Steve Van GiesonWitnessType: Plugging Operations Partially WitnessedDate/Time Plugging Completed: 08/16/2000 10:30 AM

Actual Plugging Report:

A CIBP was set at 4050. The 5 1/2 casing was recovered from 2980' and pulled to 724', where 35sxs of cement was spotted. The casing was pulled to 320' where cement was circulated to surface. The remaining pipe was pulled from the wellbore and the cement was returned to surface. Plate welded on top of surface pipe.

RECEIVED
KCC DISTRICT #2

AUG 31 2000

WICHITA, KS

Remarks: Class A CementAnhydrite Plug: No

BottomPlug:

DakotaPlug: No

Plugged through:

I (did / did not) observe this plugging.

INVOICED

Signed

(TECHNICIAN)

DATE

9/8/00

INV. NO.

2001060617