

1100331

TO: STATE CORPORATION COMMISSION

API NUMBER 15-129-10,253-0000
SW SW NE SEC. 17, T 33 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ELLIS B WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON 106.93

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 3290' FEET

OPERATOR: OXY USA INC

PRODUCTION CSG: SIZE 5 1/2" @ 3287' WITH 250 SX

NAME AND BOX 2528

SURFACE CASING: SIZE 8 5/8" @ 600' WITH 300 SX

ADDRESS LIBERAL, KS 67950-2528

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CASING PULLING SERVICE LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 07 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TERRY YODER

(COMPANY NAME) SARGENTS CASING PULLING SERVICE (PHONE) 316-624-7455

WERE: PERFS AT 3290-3288

1ST PLUG SPOT 50 SX WITH 600# HULLS AT 2900'. 2ND PLUG CEMENT BACK SIDE WITH 130 SX

CEMENT. PRESSURE UP TO 550#. 3RD PLUG FILL 4 1/2" LINER FROM 750' TO SURFACE WITH 75 SX

CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 08 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 50 SX CEMENT WITH 600# HULLS AT 2900'. 2ND PLUG CEMENT BACK SIDE WITH 130

SX CEMENT. PRESSURE UP TO 550#. 3RD PLUG FILL 4 1/2" LINER FROM 750' TO SURFACE WITH 75

SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION

REMARKS: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

FEB 18 2000

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

DATE 2/18/00 SIGNED

Gary Winters
(TECHNICIAN)

FORM CP-2/3

INV. NO. 061266