

To: 1 052179  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
180 S. Market, Room 2078  
Wichita, KS 67202

10-12 API NUMBER 15-189-22,244-0000  
C SW NE, SEC. 22, T 33 S, R 38 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003  
Operator: McCoy Petroleum Corp.  
Name:  
Address 3017 N. Cypress Dr.  
Wichita, KS 67226-4003

3300 feet from S section line  
1980 feet from E section line  
Lease Name Coulter A Well # 1-22  
County Stevens 204.75  
Well Total Depth 6300 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1705

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sweetman Drilling, Inc. License Number 5658  
Address 3017 N. Cypress Dr., Wichita, KS 67226-4003

Company to plug at: Hour: \_\_\_\_\_ Day: 12 Month: -10 Year: 1997  
Brad

Plugging proposal received from \_\_\_\_\_  
(company name) Sweetman Drilling, Inc. (phone) 316-634-6151

Work: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at Hugoton/Council Grove with 100 sx cement, 2nd plug at 1740' with 50 sx cement,  
3rd plug at 700' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:55 p.m. Day: 12 Month: 10 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement,  
2nd plug at 1740' with 50 sx cement,  
3rd plug at 700' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 4 1997  
10-16-97  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

I (XXX) did not observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

**INVOICED**  
DATE OCT 23 1997  
INV. NO. 49281

EFFECTIVE DATE: 9-4-97

State of Kansas

189-22,244

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

SGA? YES  NO

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date: September 15 1997  
Month Day Year

Spot East  
 C  SW  NE Sec 22 Twp 33s Rng 38w  West

OPERATOR: License # 5003  
Name: McCoy Petroleum Corporation  
Address: 3017 N. Cypress Street  
City/State/Zip: Wichita, KS 67226-4003  
Contact Person: Brent B. Reinhardt  
Phone: (316) 636-2737

3300 feet from South / North line of Section  
1980 feet from East / West line of Section  
IS SECTION  REGULAR  IRREGULAR?  
(NOTE: Locate well on the Section Plat on Reverse Side)

County: Stevens  
Lease Name: COULTER "A" Well # 1-22  
Field Name: Wildcat

CONTRACTOR: License # 5658  
Name: Sweetman Drilling, Inc.

\* Is this a Propped/Spaced Field?  yes  no  
Target Formation(s): Morrow  
Nearest lease or unit boundary: 660'  
Ground Surface Elevation: Estm. 3160' feet MSL  
Water well within one-quarter mile:  yes  no  
Public water supply well within one mile:  yes  no  
Depth to bottom of fresh water: 480'  
Depth to bottom of usable water: 560'  
Surface Pipe by Alternate:  1  2  
Length of Surface Pipe Planned to be set: 580'  
Length of Conductor Pipe required: None  
Projected Total Depth: 6600'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
 well  farm pond  other

Well Drilled For: Well Class: Type Equipment:  
 Oil  Enh Rec  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OWWO  Disposal  Wildcat  Cable  
 Seismic; # of Holes  Other

If OWWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore?  yes  no

If yes, true vertical depth \_\_\_\_\_

Bottom Hole Location \_\_\_\_\_

Exp. 3/9/98

Permit to be applied for by Drilling Contractor.  
Will Cores be Taken?  yes  no  
If yes, proposed zone: 580' Alt. I Req.

\* PROPPED AND SPACED IN CHASE  
AND COUNCIL BRINE.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

STATE OREGON COMMISSION

OCT 16 1997

CONSERVATION DIVISION  
Wichita, Kansas

Brad

SPUD DATE 9-30-97 INIT. SP

LENGTH SURFACE PLANNED 1700+

RESERVE PIT STATUS- REMOVE FLUID \_\_\_\_\_  
after salt sect. bbls. when done bbls \_\_\_\_\_

ATHOLED AHEAD?  Y  N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 1/2" @ 1705 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- B- \_\_\_\_\_ ELEVATION \_\_\_\_\_

DEPTH 6300 FORMATION M155

PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_

Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Plug./Council @ 3200 Ft. W/ 100 SX

Anhydrite Base @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

1/2 Base Anhyd. @ 700 Ft. W/ 40 SX

1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Bottom Surface @ 1740 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
\_\_\_\_\_ Hauling \_\_\_\_\_

TECHNICIAN AL DATE 10-11-97

TYPE OF CEMENT 60/40 6876

TARTING TIME \_\_\_\_\_ (AM/PM) DATE \_\_\_\_\_  
COMPLETION TIME 5:55 (AM/PM) DATE 10-12-97

CEMENT COMPANY Halsbury