

To: 1 020408
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-1
API NUMBER 15- 189-20,726 - 0000
C NE NE, SEC. 22, T. 33 S, R. 38 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address: 2319 N. Kansas
Liberal, KS 67901

4620 feet from S section line
660 feet from E section line

Lease Name Coulter #1 UniWell # 3
County Stevens 202.02
Well Total Depth 6216 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 1730

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mobil Oil Corp. License Number 5208

Address 2319 N. Kansas, Liberal, KS 67901

Company to plug at: Hour: 2 p.m. Day: 30 Month: 9 Year: 19 91

Plugging proposal received from Tommy Romero

(company name) Mobil Oil Corporation (phone) 316-544-5530

were: 5 1/2" at 6215' w/250 sx cement, DV tool at 3150' w/250 sx cement, PBTD 6159'

Perfs at 6080-87'

1st plug set CIBP at 6070' with 2 sx cement on top,

2nd plug circulate hole with mud. Run tubing to 3200' and pump 110 sx cement,

3rd plug pull tubing out, cut casing at 1800', run 100 sx cement, 4th plug pull casing to 700' and pump 140 sx,

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

5th plug pull casing to 80' and pump 25 sx cement.

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 7 p.m. Day: 1 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6050' with 2 sx cement on top, loaded hole with gel mud, 2nd plug pumped 110 sx cement at 3210',

3rd plug pumped 50 sx cement at 1780-1632',

4th plug pumped 75 sx cement at 700-480',

5th plug pumped 25 sx cement at 60-0'.

All plugs displaced with mud.

Remarks: Used Class H cement by Halliburton. Recovered 1788' of 5 1/2" casing.

INVOICED (Additional description is necessary, use BACK of this form.)
I (did / XXXXXXXX) observe this plugging.

DATE 11-6-91
INV. NO. 33630

Signed Glenn R. Barber (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 03 1991
CONSERVATION DIVISION
Wichita, Kansas