

To: 100138
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

6-2

API NUMBER 15-129-20,936-0000

App. SE NW SE, SEC. 26, T 34 S, R 40 W XX

1390 feet from S section line

1390 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4549

Lease Name O'Conner A Well # 1

Operator: Anadarko Petroleum Corporation

County Morton 93.76

Name & Address P.O. Box 351.

Well Total Depth 2885 feet

Address

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 520

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49 BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12 p.m. Day: 2 Month: 6 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

was: 5 1/2" at 2884', cement circulated to surface, PBTD 2864', Perfs at 2537-2700'

1st plug through tubing with 20 sx cement and 2 sx hulls on bottom,

2nd plug at 1500' with 40 sx cement,

3rd plug at 520'- surface with 70 sx cement.

Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:30 p.m. Day: 2 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug spotted 25 sx cement with 2 sx hulls at 2537-2337', tubing in hole, 6-10-97

2nd plug spotted 40 sx cement through tubing at 1730', displace with gel,

3rd plug spotted 70 sx cement at 570' through tubing, cement circulated to surface.

Pulled tubing, 4th plug topped off with 5 sx cement.

Remarks: Used common cement by Sargent & Horton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / XXXXXX) observe this plugging.

DATE JUN 12 1997

INV. NO. 48324

Signed Gary Winters
(TECHNICIAN)