

1 060553

15-119-10208 *Poco*

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Comp. 8-28-59  
C SW NE, SEC. 32, T 33 S, R 29 W/EX

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name W. B. Fox Well # 4

Operator: Texaco, USA

County Meade 194.51

Name & Address P. O. Box 2420

Well Total Depth 5985 feet

Tulsa, OK 74102

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1500

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:00 pm Day: 22 Month: April Year: 1985

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 5985' PBTD 5843' Perfs at 5779-5859' Junk at 1638' cannot go deeper

1st plug pump 2 sx hulls and 30 sx cement to bottom

RECEIVED  
STATE CORPORATION COMMISSION

Pump through 5 1/2" with mud between plugs

MAY 02 1985

2nd plug at 1530' with 50 sx cement

CONSERVATION DIVISION  
Wichita, Kansas

3rd plug at 480' with 30 sx cement  
solid bridge

4th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi  
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 5:00 pm Day: 22 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 30 sx cement to bottom, 2nd plug  
at 1530' with 50 sx cement, 3rd plug at 480' with 30 sx cement, 4th & 5th plugs - solid  
bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 2408' 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(if this did not) observe this plugging.

DATE

5-8-85

Signed

*Paul A. Luthi*  
(TECHNICIAN)

INV. NO.

8042

2-22 MAY 22 1985