

1 060549

15-119-10212-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 12-27-57

NW NE, SEC. 32, T 33 S, R 29 W/E

4620 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name Fox Well # 3

Operator: Texaco, USA

County Meade 193.38

Name & Address P. O. Box 2420

Well Total Depth 5950 feet

Tulsa, OK 74102

Conductor Pipe: Size 16 feet 41

Surface Casing: Size 10 3/4 feet 1530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:00 pm Day: 23 Month: April Year: 19 85

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 10 3/4" at 1530' PBD 3431' 7" at 5949' Perfs at 3212-3328' Retainer at 3431'

RECEIVED

STATE CORPORATION COMMISSION

1st plug pump 2 sx hulls and 30 sx cement to bottom

Pump through 7" with mud between plugs

2nd plug at 1560' with 65 sx cement

MAY 02 1985

3rd plug at 480' with 40 sx cement

solid bridge

CONSERVATION DIVISION

4th plug hulls - plug at 40' -- cement to surface with 15 sx cement

Wichita, Kansas

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00 pm Day: 23 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 30 sx cement to bottom, 2nd plug

at 1560' with 65 sx cement, 3rd plug at 480' with 40 sx cement, 4th & 5th plugs - solid

bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

Remarks: Used common sacked cement by Sargents. Recovered 1608' 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-8-85

Signed Paula Luthi (TECHNICIAN)

INV. NO. 8043 4-23 MAY 22 1985