

1 060547

15-119-00026A0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Comp. 8-26-56

SE NE, SEC. 32, T. 33 S, R. 29 W/EX

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name Fox Well # 1

Operator: Texaco, Inc. USA

County Meade 191.56

Name & Address P. O. Box 2420

Well Total Depth 5894 feet

Tulsa, OK 74102

Conductor Pipe: Size 16 feet 39

Surface Casing: Size 10 3/4 feet 1490

TEMPORARILY ABANDONED
Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 12:30 pm Day: 20 Month: April Year: 1985

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 7" at 5891' PBTD 5863' Perfs at 5810-5838'

1st plug pump 2 sx hulls and 30 sx cement to bottom.

Pump through- 7" with mud between plugs

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at 1520' with 65 sx cement solid bridge 3rd plug at 480' with 40 sx cement

APR 23 1985

4th plug hulls - plug at 40' -- cement to surface with 15 sx cement

CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Proposal Received by Paul A. Luttie

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 pm Day: 20 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 30 sx cement to bottom, 2nd plug

at 1520' with 65 sx cement, 3rd plug at 480' with 40 sx cement, 4th & 5th plugs - solid

bridge - hulls - plug at 40' -- cement to surface with 15 sx cement.

Remarks: Recovered 2608' 7" casing. Used common sacked cement by Sargent's
(If additional description is necessary, use BACK of this form.)

VOIDED (do not) observe this plugging.

Signed Paul A. Luttie
(TECHNICIAN)

DATE 5-6-85

NO. 7949

MAY 22 1985