

15-119-10013-0000

1 060554

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Not available  
C NE NW, SEC. 32, T 33 S, R 29 W/E

4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7135

Lease Name Fox Well # 1

Operator: Wendell B. Fox  
Name & Address: P. O. Box 55  
Plains, KS 67869

County Meade 194.03

Well Total Depth 5970 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1600

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:00 pm Day: 26 Month: April Year: 1985

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 5970' PBD 5938' Perfs at 5798-5832'

1st plug pump 2 sx hulls and 25 sx cement to bottom

Pump through 5 1/2" casing with heavy mud between plugs

2nd plug at 1650' with 35 sx cement

3rd plug at 700' with 25 sx cement  
solid bridge

4th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi  
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 5:00 pm Day: 26 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom, 2nd plug  
at 1650' with 35 sx cement, 3rd plug at 700' with 25 sx cement, 4th & 5th plugs - solid  
bridge -hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used common sacked cement by Sargent's Recovered 2815' 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(SEE / OR NOT) observe this plugging.

DATE 5-7-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 7967 JUN 6 1985 JUL 1 8 1985