

318 R

To: 1 090033
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- 119-20,624 -0000
S/2 NE SE, SEC. 3, T 34 S, R 26 W/E
1650 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

660 feet from E section line
Lease Name Iona Goodnight Well # 2

Operator: Texaco, Inc. for Texaco Producing,
Name & Address P.O. Box 2700
Pampa, TX 79066-2700

County Meade License Number 194.25
Well Total Depth 5977 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1226

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS

Company to plug at: Hour: 2:30 p.m. Day: 12 Month: 12 Year: 19 90

Plugging proposal received from Sargent's Casing Pulling Service (company name) License Number 6547 (phone) 316-624-7455

were: 4 1/2" at 5969', PBD 5750', Perfs at 5726-5908' (6 sets)

- 1st plug pump 25 sx cement on bottom,
- 2nd plug spot 30 sx cement at freepoint,
- 3rd plug spot 50 sx cement at 1250', 4th plug spot 50 sx cement at 600',
- 5th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 12 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement on bottom to cover perfs from 5798-5726',

2nd plug spotted 50 sx cement at 1250' through 2" tubing,

3rd plug pulled to 600', spotted 48 sx cement,

4th plug pulled to 40', spotted 10 sx cement.

Cement circulated.

Remarks: Used common cement by Sargent's. Recovered 2420' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DEC 21 1990

INVOICED (if you observe this plugging.)

DATE JAN 17 1991

Signed [Signature] (TECHNICIAN)

INV. NO. 30519