

1031538

TO: STATE CORPORATION COMMISSION

API NUMBER 15-025-21,192 - 0000
E/2 NW SE SEC. 33, T 34 S, R 25 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME COX "33" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY CLARK 35.00

OPERATOR LICENSE # 32459

WELL TOTAL DEPTH 500 FEET

OPERATOR: MEWBOURNE OIL COMPANY PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 7698 SURFACE CASING: SIZE "@ ' WITH SX

ADDRESS TYLER, TX 75711 CONDUCTOR CSG: SIZE 20" @ 40'.

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR BIG A DRILLING LICENSE NUMBER 31572

ADDRESS P.O. BOX 1856 LIBERAL, KS 67905-1856

COMPANY TO PLUG AT: HOUR: 1:00 A.M. DAY: 15 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) BIG A DRILLING (PHONE) 316-624-1904

WERE: 12 1/4" HOLE AT 500'. 17 1/2" HOLE AT 225'. LOST CIRCULATION JUST BELOW 20" CONDUCTOR.

1ST PLUG AT 200' WITH 70 SX CEMENT. TAG TOP OF CEMENT AT 160' AT 5:00 A.M. ON 01/15/00.

2ND PLUG AT 160' WITH 145 SX CEMENT. TAG TOP OF CEMENT AT 55' AT 9:00 A.M. ON 01/15/00.

3RD PLUG AT 55' WITH 100 SX CEMENT. TAG TOP OF CEMENT AT 14'. 4TH PLUG TO CIRCULATE

RAT HOLE WITH 15 SX CEMENT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

INVOICED

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

DATE 1/25/00

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL NONE X

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 15 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG AT 200' WITH 70 SX CEMENT. TAG TOP OF CEMENT AT 160' AT 5:00 A.M. ON 01/15/00.

2ND PLUG AT 160' WITH 145 SX CEMENT. TAG TOP OF CEMENT AT 55' AT 9:00 A.M. ON 01/15/00.

3RD PLUG AT 55' WITH 100 SX CEMENT. TAG TOP OF CEMENT AT 14'. 4TH PLUG TO CIRCULATE

RAT HOLE WITH 15 SX CEMENT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED CLASS C CEMENT WITH 3% CC BY B.J. TITAN.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Steve Durrant (TECHNICIAN) FORM CP-2/3

RECEIVED STATE CORPORATION COMMISSION

JAN 25 2000 1-25-00

CONSERVATION DIVISION Wichita, Kansas

