

1060839

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,766 - 0000
C SW, SEC. 31, T 34 S, R 25 W XX
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060
Operator: Zinke & Trumbo, Ltd.
Name & Address 111 West 5th, Suite 220
Tulsa, OK 74103

Lease Name Berends Well # 1-31
County Clark 204.75
Well Total Depth 6300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1514

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:30 am Day: 18 Month: March Year: 1986

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6300' PBT 6255' Perfs at 5882-5904' Pump through 4 1/2" casing with mud between plugs

1st plug pump 30 sx cement and 2 sx hulls to bottom and push plug to 5700'

2nd plug at 1554' with 50 sx cement

3rd plug at ^{solid bridge} 600' with 25 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 18 Month: March Year: 1986

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement and 2 sx hulls to bottom pushing

plug to 5700', 2nd plug at 1554' with 50 sx cement, 3rd plug at 600' with 25 sx cement,

4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 4205' 4 1/2" casing. Used common cement by Sargent's
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986

INV. NO. 13041

3-18

MAR 20 1986 Signed Paul A. Luthi
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84