

1 060755

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,285 - 0000

C NW SE, SEC. 28, T 34 S, R 25 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6378

Lease Name Walker Well # 1-28

Operator: Hawkins Oil & Gas, Inc.

County Clark 206.38

Name & Address P. O. Box 1282

Well Total Depth 6350 feet

Liberal, KS 67901

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 684

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 8:00 am Day: 2 Month: January Year: 19 86

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6148' PBD 6110' Perfs at 6076-5786' Plug through 4 1/2" with mud between
1st plug pump 25 sx cement & 2 sx hulls at 6086 to 5700'. plugs

2nd plug pump 40 sx cement at 1400' to 1300'

3rd plug pump 40 sx cement at 700' to 600'
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:00 pm Day: 2 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 6086' with 25 sx cement, 2nd plug at 1400' with 40 sx
cement, 3rd plug at 700' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used common cement by Sargent's Recovered 4525' 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed Paul A. Lacey
(TECHNICIAN)

DATE JAN 13 1986

JAN 6 1986

INV. NO. 11935
1-2

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84