

To: 1 060746  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,420 -0000  
C SW, SEC. 24, T 34 S, R 25 W/EX  
1320 feet from (S) section line  
3960 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5760  
Operator: Irex Corporation  
Name & Address 1311 17th, Suite 800  
Denver, CO 80202

Lease Name Cox Well # 1  
County Clark  
Well Total Depth 6300 204.75 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 705

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Reeves & Wilson, Inc. License Number 6083  
Address P. O. Box 963, Woodward, OK 73802

Company to plug at: Hour: 10:00 am Day: 17 Month: December Year: 19 85

Plugging proposal received from Sid Wilson  
(company name) Reeves & Wilson (phone) 405-256-6023

were: 4 1/2" at 6278' PBTD 6237' Perfs at 5685-5711'; 5732-40'; 5885-93'; 6009-18'; 6161-73'  
Pump through 4 1/2" casing with mud between plugs  
1st plug set CIBP at 5630' with 2 sx cement  
2nd plug at 1050' with 50 sx cement  
3rd plug at 750' with 50 sx cement  
solid bridge  
4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 17 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5630' with 2 sx cement, 2nd plug at 1050' with  
50 sx cement, 3rd plug at 750' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls  
plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 2068' 4 1/2" casing. Used Class H cement by Reeves & Wilson  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE DEC 20 1985

INV. NO. 11672

12-17

observe this plugging.  
STATE CORPORATION COM

DEC 20 1985

CONSERVATION DIVISION

Signed Paul A. Luthi  
(TECHNICIAN)