

To: R 2051915 3-30
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-025-10076-0000
API NUMBER 15- Completion date 10/57
C SW , SEC. 22, T 34 S, R 25 W/E
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7142
Operator: Black Dome Energy Corporation
Name: 1536 Cole Boulevard, Ste. 325
Address: Golden, CO 80401

Lease Name Theis Well # J-3
County Clark 190.45
Well Total Depth 5860 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1214

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 9 a.m. Day: 30 Month: 3 Year: 19 95

Plugging proposal received from Maurice Prosser
(company name) Black Dome Energy Corporation (phone) 316-672-5135

Notes: 4 1/2" at 5860' w/200 sx cement, PBTD 5790', Perfs at 5696-5712'
1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 12 sx gel, 50 sx cement, 8 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 9:45 a.m. Day: 30 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 5640' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped down the 8 5/8" with 300 lbs. hulls, 12 sx gel, 50 sx cement, 8 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and numped 150 sx cement.
Maximum pressure 850 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3997' of 4 1/2" casing.
(additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.
DATE 4-2-95
INV. NO. 42517

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAD
3-31-95
CONSULTATION DIVISION
WICHITA, KANSAS