

To: 051150
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-9
API NUMBER 15- 025-21,026 - 0000

TECHNICIAN'S PLUGGING REPORT
Operator License # 5254

C S/2 SW, SEC. 18, T 34 S, R 25 W/E
660 feet from S section line
3960 feet from E section line

Operator: Midco Exploration, Inc.
Name & Address 200 East 1st Street, Suite 411
Wichita, KS 67202

Lease Name Goodnight Well # 1
County Clark 190.94
Well Total Depth 5875 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 786

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Company, Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 8:30 p.m. Day: 9 Month: 4 Year: 19 89

Plugging proposal received from Harvey Moore
(company name) Abercrombie Drilling Company, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 800' with 50 sx cement, 2nd plug at 400' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1989
4-13-89
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 p.m. Day: 9 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement,
2nd plug at 400' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-24-89

INV. NO. 24450

Signed Richard M. Lacey
(TECHNICIAN)