

1 020852

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,016-0000
200' N & E of
C SW, SEC. 14, T 34 S, R 25 W
1450 feet from S section line
1450 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5254
Operator: Midco Exploration, Inc.
Name & Address 453 S. Webb Rd., Ste. 100
Wichita, KS 67207

Lease Name Klinger Well # 1
County Clark
Well Total Depth 5895 191.59 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 725

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 11 a.m. Day: 7 Month: 4 Year: 19 95

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5775' w/200 sx cement, PBTD 5835', Perfs at 5641-65'

- 1st plug pump in 4 1/2" with 200 lbs. hulls and 20 sx cement, displace to 5400',
- 2nd plug at 750' with 50 sx cement,
- 3rd plug at 400' with 40 sx cement,
- 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 p.m. Day: 10 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement at perfs,
2nd plug shot pipe off at 4545', loaded hole with mud and pumped 50 sx cement at 750',
3rd plug pumped 40 sx cement at 400',
4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 4545' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 4-26-95
INV. NO. 42699

Signed Alexander R. Barber
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1995
CONSERVATION DIVISION
WICHITA, KANSAS