

15-119-10329-0000

1050311

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 3-7-63

C NW NW , SEC. 5 , T 34 S, R 29 W ~~XX~~
4620 feet from ~~XX~~ SE Corner of section 11e
4620 feet from ~~XX~~ W SE Corner of section 11e

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087
Operator: Texas Energies
Name & Address: Box 947
Pratt, KS 67124

Lease Name Adams Well # 1-5
County Meade
Well Total Depth 6070 212.45 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1483

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Texas Energies License Number 5087

Address Box 947, Pratt, KS 67124

Company to plug at: Hour: 10:00 am Day: 10 Month: August Year: 19 84

Plugging proposal received from Dick Harper

(company name) Texas Energies (phone) 316-672-7514

were: 4 1/2" set at 5955' Perfs at 5885-95'

1st plug sand back to 5820' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 25 sx cement, 10 sx gel, 50 sx cement, 10 sx gel and 100 sx cement.

Pump 150 sx cement down the annulus

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:25 pm Day: 9 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5955' Peffs at 5885-95'

pumped 3 sx hulls, 10 sx gel, 75 sx cement, 10 sx gel and 75 sx cement

Pumped 150 sx cement down the annulus

Maximum pressure 1600 psi and shut in pressure 35 psi.

Remarks: No pipe recovery. Cemented by Buie No. 3128.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (xxx) did not observe this plugging.

DATE 8-17-87

Signed Richard W. Lacey
(TECHNICIAN)
50

INV. NO. 3236

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1984
CONSERVATION DIVISION
Wichita, Kansas