

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21067-00-00  
Spot: SENW Sec/Twnshp/Rge: 4-34S-29W  
1980 feet from N Section Line, 1980 feet from W Section Line  
Lease/Unit Name: IRISH FLATS Well Number: 1-4  
County: MEADE Total Vertical Depth: 6350 feet

Operator License No.: 30604  
Op Name: RAYDON EXPLORATION, INC.  
Address: 9400 N. BROADWAY #400  
OKLAHOMA CITY, OK 73114

Conductor Pipe: Size 20 feet: 50 \$206.38  
Surface Casing: Size 8.625 feet: 1616 WITH 750 SX CMT  
Production: Size 5.5 feet: 6349 WITH 170 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/09/2002 8:45 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5800' WITH 2 SX CMT. 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. 15 SX GEL ON SIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/09/2002 12:15 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 6200'. PERFS AT 5842-5848'. CIBP @ 5800' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 1640' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. STAYED FULL.

RECEIVED  
SEP 16 2002  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT LILLARD. RECOVERED 5355' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed   
(TECHNICIAN)

INVOICED SEP 11 2002

DATE 9-18-02  
VV. NO. 2003060512

