

1 100036

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 119-20,652-0000
140' SE of
C SE NE, SEC. 2, T 34 S, R 29 W/8
3201 feet from S section line
561 feet from E section line

4-5

TECHNICIAN'S PLUGGING REPORT
Operator License # 5205
Operator: Mid-Continent Energy Corp.
Name: _____
Address 105 S. Broadway, Ste. 900
Wichita, KS 67202

Lease Name Cordes Well # 1
County Meade 208.68
Well Total Depth 6421 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1475

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address: P.O. Box 506, Liberal, KS 67901-0506

Company to plug at: Hour: 9 a.m. Day: 5 Month: 4 Year: 1996

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 5 1/2" at 6381' w/425 sx cement, PBD 5800', Perfs at 5243.5-51, 5748-54, 5830-36'

1st plug pump 3 sx hulls and 30 sx cement, displace hole with drilling mud,

Spot plugs through 5 1/2" casing: 4-9-96

2nd plug at 1500' with 50 sx cement,

3rd plug at 600' with 40 sx cement, 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 5 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement with 3 sx hulls at 5243',

2nd plug at 1500' with 50 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3010' of 5 1/2" casing.
If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.
DATE APR 18 1996

Signed Gary Winters (TECHNICIAN)

INV. NO. 45352 JUN 27 1996 JUL 17 1996