

I think you have a rather copy of this in your files. He received the plugged bill just after the well was plugged

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-10013-0000

LEASE NAME FOX

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. C-NE-NW Ft. from S Section Line
office within 30 days. _____ Ft. from E Section Line

LEASE OPERATOR W.B. Fox

SEC. 32 TWP. 33 RGE. 29W (E) or (W)

ADDRESS Plains, Kansas 67869

COUNTY Meade

PHONE# (316) 563-7349 OPERATORS LICENSE NO. 7135

Date Well Completed _____

Character of Well Farm Gas

Plugging Commenced 4-24-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-27-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Morrow Depth to Top 5797 Bottom 5838 T.D. 5938

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1600	none
				5 1/2	5970	2806

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 25 sks. of cement & 2 sks. of hulls @ 5832 to 5580
Pump 35 sks. of cement @ 1650 to 1550
Pump 25 sks. of cement @ 700 to 600
Put 10 sks. of cement @ 40 to 0 Cut off & cap 8 5/8 3' below ground level
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Meade, ss.

Wendell B. Fox (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein and the log of the above-described well as filed that the same are true and correct.

NOTARY PUBLIC - State of Kansas
ANITA M. KIDDER
My Appt. Exp. 10-15-86

RECEIVED
AUG 6 1985
8-06-85

(Signature) Wendell B. Fox

(Address) Box 55 Plains, Kansas 67869

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 85
Wichita, Kansas

Anita M. Kidder
Anita M. Kidder Notary Public

My Commission Expires: 10-15-86

GABBERT-JONES DRILLING CO., INC.
WICHITA, KANSAS
DRILLER'S WELL LOG

FOX #1
C NE NW SECTION 32-33-29W
MEADE COUNTY, KANSAS
COMMENCED 8-1-57
COMPLETED 8-31-57

DEPTH		FORMATION	REMARKS
FROM	TO		
0	20	SURFACE SOIL & CLAY	
20	630	RED BED & SAND	
630	910	RED BED & SHALE	
910	1090	RED BED	
1090	1400	SAND	
1400	1470	LIME	
1470	1520	LIME & SHALE	
1520	1618	LIME	RAN 1600' OF 8 5/8" CASING, CEMENTED W/880 BAGGS CEMENT.
1618	1850	RED BED	
1850	2225	SHALE & SHELLS	
2225	2385	SHALE & LIME	
2385	2460	LIME	
2460	2556	SHALE	
2556	2618	SHALE & SHELLS	
2618	3140	LIME & SHALE	
3140	3281	LIME	
3281	3345	LIME & SHALE	
3345	3399	LIME & SHALE WITH CHALK	
3399	3425	SHALE & CHALK	
3425	3612	CHALK & LIME	
3612	3840	LIME & SHALE WITH CHALK	
3840	4025	LIME & SHALE	
4025	4179	SHALE	
4179	4233	SHALE & LIME	
4233	4444	SHALE	
4444	4601	SHALE & LIME	
4601	4640	LIME	
4640	4770	LIME & SHALE	
4770	4811	LIME	
4811	4838	LIME & SHALE	
4838	5015	LIME	
5015	5096	LIME & SHALE	
5096	5143	SAND	
5143	5161	SHALE	
5161	5180	LIME & SHALE	
5180	5223	SHALE	
5223	5237	SHALE & PYRITE	
5237	5768	LIME & SHALE	
5768	5792	SHALE	
5792	5858	LIME	
5858	5907	LIME	
5907	5970	LIME	
5970	TD		RAN 5960' OF 5 1/2" CASING, CEMENTED W/75 BAGGS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1985
CONSERVATION DIVISION
Wichita, Kansas

I, H. F. JONES, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE FOX #1

H F Jones