

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Meade

County. Sec. 33 Twp. 33S Rge. 29W (E) (W)

Location as "NE/CNW/SW" or footage from lines Center SW NW

Lease Owner The Texas Company

Lease Name J. H. Collingwood Well No. 1

Office Address 614 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed September 12 19 56

Application for plugging filed September 12 19 56

Application for plugging approved (Verbal 9-12) September 13 19 56

Plugging commenced September 12 19 56

Plugging completed September 13 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 5915 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	26'	0'
				10-3/4"	1514'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED AS FOLLOWS:

Heavy Mud 5915' to 500'
Plug & 1 Sack Hulls @ 500'
35 Sacks Cement 500' to 430'
Heavy Mud 430' to 30'
Plug & 1 Sack Hulls @ 30'
10 Sacks Cement 30' to Bottom of Cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Noble Drilling Company

Address Stanolind Building, Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. C. Harrell (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell

614 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of September, 19 56

My commission expires September 20, 1956

Howard Kistler Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 33 T. 33 R. 29W
BOOK PAGE 98 LINE 26

OCT 9 1956
10-09-56
CONSERVATION DIVISION
WICHITA, KANSAS

LOG OF WELL

15-119-1021070000
State of Oklahoma

FORM PO-214 SHEET 1 (4-54) 35M

J. H. COLLINGWOOD NO. 1

SHEET **1**

OWNER **The Texas Company** DIVISION **Oklahoma** DATE MADE **September 21, 1956**
 DISTRICT **Kansas** LEASE **J. H. Collingwood** WELL NO. **1**
 STATE **Kansas** COUNTY OR PARISH **Meade** TWP. **33S** RANGE **29W** SEC. **33**
 LOCATION OF WELL **C. SW NW**

COMMENCED RIGGING UP **8-16-56** COMMENCED DRILLING **8-16-56** COMPLETED DRILLING **9-12-56**
 DAY DRILLER _____ NIGHT DRILLER _____ CONTRACTOR **Noble Drlg. Co.**
 CABLE FROM _____ TO _____ ROTARY FROM **0'** TO **5915'** COMPLETE RIG NO. **2594**
 TOTAL DEPTH **5915'** MEASURED BY **M. C. Harrell** ELEVATION **DF - 2591**
GL - 2584

CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS		
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MAKE	KIND	LENGTH	SET AT
16"	65#	26'										PT.
10-3/4"	32.75#	1514'										PT.
												PT.
												PT.
												PT.
												PT.
												PT.
												PT.
												PT.

16" casing set at 31' with cement. Cement circulated.
 10-3/4" casing set at 1498' (See remarks dated 8-18 & 20-56)

WAS CASING CEMENTED? _____ IF SO, HOW MANY SACKS OF CEMENT USED? _____
 LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____
 HOW PUT TOGETHER _____ COUPLING _____ FLUSH-JOINT _____ INSERTED _____
 REMARKS: _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.

Completed Plugging 9-13-56

FLOWING, PUMPING, GASSER OR DRY **Dry** PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____
 IF GAS WELL, OPEN FLOW CAPACITY _____ SHUT IN PRESSURE _____ ROCK PRESSURE _____
 KIND OF SHOT _____ SIZE OF SHOT, QUARTS _____
 NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____
 LENGTH OF SHELLS _____ FEET _____ INCHES _____ TOP OF SHOT _____
 BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____
 TOTAL DEPTH OF WELL _____ NUMBER OF SHOT _____ PRODUCTION BEFORE SHOT _____ BBLG. PER DAY _____
 PRODUCTION AFTER SHOT _____ BBLG. PER DAY. SHOT FURNISHED BY _____
 NAME OF SHOOTER _____ SHOT INSPECTED _____ BY _____ (COMPANY EMPLOYEE)
 COMMENCED DRILLING DEEPER _____ COMPLETED _____ DRILLING DEEPER _____
 TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____

J. H. Collingwood #1
Unnamed Pool
TD 5915'
Completed Drilling 9-12-56
Completed Testing 9-13-56

PLUGGING

WELL WAS DRY, STATE UNDER REMARKS WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
 IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT, WRITE ON BOTTOM OF LAST SHEET OF LOG.

FILE SEC. **33 T23** LINE **26**
 BOOK PAGE **98** LINE **26**

RECEIVED

OCT 9 1956

RESERVATION DIVISION

TOTAL NUMBER OF SHEETS _____

State

LOG OF WELL

SHEET NO. _____

District **Kansas** Owner **The Texas Company Farm J. H. Collingwood Well No. 1**

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
REMARKS:					
8-18-56					Set 10-3/4" casing at 1498' with 900 sacks cement, 2% CC. Cement circulated.
8-20-56					Ran Log and found 14' of 10-3/4" pipe which had broken off surface string, top at 1514', bottom at 1528'. Spotted 250 sacks cement, 10% sand, 2% CC. After cement set, drilled out cement and around broken piece of pipe.
9-7-56					Lost circulation for 3-1/2 hours at 5417'.
9-11-56					Took Core #1 from 5825-70', recovered 45'.
9-13-56					Drilled to 5915'. Ran Halliburton Log to 5909'. Well non-commercial. Plugged and abandoned.
TOPS:					
					Cimarron Dolomite-1463
					Heebner-----4414
					Toronto-----4464
					Lansing-----4584
					Marmaton-----5256
					Cherokee-----5454
					Atoka-----5608
					Morrow-----5789
					Morrow Sand-----5838
					Mississippi-----5894

PLUGGING
 FILE SEC 33 T. 33 R. 29W
 BOOK PAGE 98 LINE 26

RECEIVED
 STATE COMMISSION
 OCT 11 1956
 DIVISION

DRILLING LOG

The Texas Company - J. H. Collingwood Well No. 1, Sec. 33,
Twp 33 S., Rge 29 W., Meade County, Kansas.

Started: 8-15-56
 Completed: 9-12-56
 Casing: Set 10 3/4" at 1498' w/900 Sax at 9:00 AM
 8-17-56 W.O.C. 23 Hours
 Plugged hole 9-12-56

0 - 395 Clay
 395 - 864 Clay - Sand, Red bed
 864 - 1228 Red bed & Blue shale
 1228 - 1461 Red Bed
 1461 - 1503 Red Bed & Sand
 1503 - 2365 Shale
 2365 - 2380 Shale & Lime
 1627 - 1760 (Sidetracking)
 1760 - 2065 Red Bed
 2065 - 2288 Red bed & shale
 2288 - 2430 Shale
 2430 - 5840 Lime & shale
 5840 - 5870 (Cored)
 5870 - 5915 TD: Lime & shale

PLUGGING
 FILE - SEC. 33 T. 33 R. 29W
 BOOK PAGE 98 - LINE 26

RECEIVED
 COMMISSION
 OCT 2 1956
 SERVICE DIVISION
 Wichita, Kansas