

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Meade County. Sec. 33 Twp. 33S Rge. XX 29(W)

Location as "NE/CNW*SW*" or footage from lines 1650' from South & 990' from East

Lease Owner Diamond Shamrock Corporation

Lease Name Donald J. Kolb Well No. 2

Office Address Box 631, Amarillo, Texas 79105

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 12-18 1958

Application for plugging filed 4-20-72 1972

Application for plugging approved 4-24 1972

Plugging commenced 5-17 1972

Plugging completed 5-19 1972

Reason for abandonment of well or producing formation No longer producing

If a producing well is abandoned, date of last production March 19 63

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves

Producing formation Morrow Depth to top 5748 Bottom 5791 Total Depth of Well 5862 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Oil	5,748'	5,791'	9 5/8"	1,550'	
				5 1/2"	5,836'	3,020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

25 sacks cement from 5,575' to 5,400'

35 sacks cement from 900' to 800'

15 sacks cement from 3' to 45'

Welded plate on top of surface casing.

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bob Sargent Casing Pulling

Address Box 506, Liberal, Kansas 67901

STATE OF Texas, COUNTY OF Potter, ss.
W. W. Killingsworth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. W. Killingsworth*

Box 631, Amarillo, Texas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 1972

PAULINE POWELL
Notary Public

My commission expires 6-1-73

Notary Public.



KOLB #2

1650' N of SL and 990' W of E, Section 33-33S-29W

Rigged up Rotary Tools 10/18/58

Ran 50 Jts. 9 5/8" 32#
Casing set @ 1550'. Cemented
w/900 sacks Posmix, 2% CC

Tore down Rotary Tools 11/16/58

Ran 31 Jts. 15 1/2# and 158 Jts
14# 5 1/2" (5871.34'). Set
@ 5836' with 60 sacks cement.

FORMATION	FROM	TO
Clay, sand & shells	0'	285'
Sand & Shale	285	625
Redbed, sand & shells	625	1035
Shale & shells	1035	1400
Shale & shells	1400	1610
Shale, shells & sand	1610	2085
Shale & lime	2085	4615
Lime w/ shale streaks	4615	4666
Lime	4666	4863
Lime & shale	4863	4899
Lime	4899	5215
Lime & shale	5215	5312
Lime	5312	5663
Lime & shale streaks	5663	5709
Lime	5709	5862 T. D.

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1972
CONSERVATION DIVISION
Wichita, Kansas

I, Don S. Packer, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 18th day of November, 1958.

Helen Y. Langston
Notary Public

My commission expires: March 26, 1959