

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Meade

County. Sec. 8 Twp. 34 Rge. 26 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 337' E & 334' N of Center

Lease Owner Northern Natural Gas Producing Company

Lease Name Rogers A-1 Well No. 1

Office Address 2223 Dodge St., Omaha, Nebraska

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/9/53 19

Application for plugging filed 12/9/53 19

Application for plugging approved 12/9/53 19

Plugging commenced 12/9/53 19

Plugging completed 12/9/53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				20"	163	None
				100 Sx Cement, circulated to top.		
				10 3/4"	1500	None
				500 Sx Cement, to within 200' of top.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well plugged with cement, 15 sacks to four (4) bottom plugs, 20 sacks on next plug and 25 sacks spotted at 600 feet, 35 sacks at cellar where approx. 10 feet pipe cut off and cement covering bottom of cellar. Heavy drilling mud between each plug.

Plugs set at 5950 - 5913  
5570 - 5533  
4730 - 4693  
3700 - 3663  
2634 - 2597  
600 - 560  
160 - 120

12-21-53  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. Jack M. Barton  
Address 2223 Dodge Street, Omaha, Nebraska.

STATE OF KANSAS, COUNTY OF STEVENS, ss.

JOHN R. STALDER

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Stalder

HUGOTON, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 16 th. day of December, 19 53

My commission expires Sept. 29, 1956


June Greenwood Notary Public.

PLUGGING  
FILE SEC 8 T 34 R 26W  
BOOK PAGE 149 LINE 7

FORMATION RECORD

NORTHERN NATURAL GAS PRODUCING COMPANY  
 NO. 1 RODGERS "A"  
 SEC. 8-34S26W  
 SW SW NE  
 EL: 2382 DF  
 2372 GL

1360-1550 Anhydrite & Salt  
 1550-2010 Redbeds, Shale & Sand  
 2010-2540 Anhydrite & Salt  
 2540-2900 Dolomite  
 2900-3930 Limestone, & Thin Shales  
 3930-4565 Varicolored Shales, Thin Limestones & Sands  
 4565-5215 Limestone with Thin Shales  
 5215-5300 Limy Shales with Limestone Streaks  
 5300-5865 Limestone & Shales  
 5865-5953 Thin Limestones, Shales & Sands  
 5953-6245 Limestones, Thin Shales  
 6245-6315 Varicolored Shales, Thin Limestones & Sands  
 6315-6370 Varicolored Shales & Sandy Limestones  
 T.D. 6370



**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JAN 8 - 1954  
 CONSERVATION DIVISION  
 Wichita, Kansas