

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-119-20624-0000

LEASE NAME Iona Goodnight

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2

1,790 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 3 TWP. 34S RGE. 26W (E) or (W)

COUNTY Meade

LEASE OPERATOR Texaco, Inc. for Texaco Producing, Inc.

ADDRESS P.O. Box 2700, Pampa, TX 79066-2700

PHONE (806) 665-1876 OPERATORS LICENSE NO. 4742

Date Well Completed 11-19-83

Character of Well Gas

Plugging Commenced 12-8-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-12-90

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 5,723' Bottom 5,908' T.D. 5977

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				16"	70	0
				8 5/8	1226	0
Chester	Gas	5,726	5908	4 1/2	5969	2420
				2 3/8		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 25 sks. of cement from 5738 to 5600

Pump 30 sks. of cement from 2400 to 2300

Pump 50 sks. of cement from 1250 to 1150 Pump 40 sks. of cement from 600 to 500

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 4' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

M. F. Kovar (for) J. M. Barnum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. F. Kovar for J. M. Barnum

STATE CORPORATION COMMISSION (Address) P. O. Box 2700, Pampa, TX. 79066-2700

SUBSCRIBED AND SWORN TO before me this 27th day of DECEMBER, 19 90

N. W. Jewell Notary Public

My Commission Expires: 1-2-91