

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2070  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-025-21192-0000

LEASE NAME Cox "33"

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1,980 Ft. from S Section Line

1,650 Ft. from E Section Line

SEC. 33 TWP. 34S RGE. 25 (E) or (W) (W)

LEASE OPERATOR Mewbourne Oil Company

COUNTY Clark

ADDRESS P. O. Box 7698, Tyler, TX 75711

Date Well Completed Not completed

PHONE (903) 561-2900 OPERATORS LICENSE NO. 32459

Plugging Commenced 1/14/00

Character of Well Lost hole, had to skid rig

Plugging Completed 1/15/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/14/00 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to Top N/A Bottom N/A T.O. 502'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED  
KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Water Sand	Water	0'	40'	20"	40'	0' MAR 15 2000

Describe in detail the manner in which the well was plugged, indicating where the plug fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Drilled w/12 1/4" bit to 502'. Lost returns. Attempted to run surface casing. POOH w/casing. Ran in w/drill pipe open-ended to P&A. Pumped 70 sx cement plug. TIH w/drill pipe & tagged cement @ 160'. Pumped 145 sx Class C cement @ 160'. Tagged cement @ 55'. Pumped 100 sx cement plug @ 55'. Tagged cement @ 17'. Plugged top of hole w/75 sx. cement. Plugged rat & mouse holes.

Name of Plugging Contractor B J Services License No. \_\_\_\_\_

Address Perryton, TX

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mewbourne Oil Company

STATE OF Texas COUNTY OF Smith, ss.

Janet Burns (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 7698, Tyler, TX 75711

SUBSCRIBED AND SWORN TO before me this 14th day of March 2000

My Commission Expires: \_\_\_\_\_  
CHERYL LITTLE  
Notary Public  
STATE OF TEXAS  
My Comm. Exp. 5-30-2002

[Signature]

(R)