

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-21203-00-00

LEASE NAME Josephine "29"

WELL NUMBER 1

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 29 TWP. 34S RGE. 25 (E) or (W)

COUNTY Clark

Date Well Completed Not completed

Plugging Commenced 4/12/00

Plugging Completed 4/12/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mewbourne Oil Company

ADDRESS P. O. Box 7698, Tyler, TX 75711

PHONE (903) 561-2900 OPERATORS LICENSE NO. 32459

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/12/00 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Attached If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom T.D. 6,075'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
See Form ACO-1 attached		0'	820'	8 5/8"	820'	0'

JUN 09 2000

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Displaced hole with 9.1 ppg mud.

Set 50 sx 60/40 Poz + 6% gel cement plug from 850-750'

Set 10 sx 60/40 Poz + 6% gel cement plug from 40 - 3'. Plugged rat hole w/15 sx cement and mouse hole w/10 sx cement.

Name of Plugging Contractor BJ Services License No. _____

Address Perryton, TX

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mewbourne Oil Company

STATE OF Texas COUNTY OF Smith, ss.

Janet Burns

(Employee of Operator) or (Operator) o


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Janet Burns

(Address) P. O. Box 7698, Tyler, TX 75711

SUBSCRIBED AND SWORN TO before me this 8th day of June, 2000

My Commission Expires _____



Cheryl Little
Notary Public

