

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-025-20, 420 - 0000

LEASE NAME Cox

WELL NUMBER: #1

660 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 24 TWP. 34S RGE. 25 or (W)

COUNTY Denver

Date Well Completed 2-13-81

Plugging Commenced 12-6-85

Plugging Completed 12-17-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR IREX CORP.

ADDRESS 1331 17th Street, Suite 800, Denver, CO 80202

PHONE#(303) 292-9900 OPERATORS LICENSE NO. 5760

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS (verbal agreement)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chester, St. Louis Depth to Top 5659' Bottom 6300' T.D. 6300'  
St. Gen.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Heebner	Shale	4330'		8 5/8"	705'	0'
Lansing	Shale	4476'		4 1/2"	6278'	2068'
Cherokee	Shale	5369'	5634'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 5635' w/50' cement on top-Shot pipe @ 2068' - Pulled to 1150' - Set 50 sx cement plug 1150'-1050' - Pulled to 805' - Set 50 sx cement plug 805'-705'  
Pulled casing - Set 10 sx surface plug 4'-40' - Cut casing - Welded on steel plate

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Reeves & Wilson, Inc. License No. 6083

Address P.O. Box 963 Woodward, OK 73802

STATE OF COLORADO COUNTY OF DENVER, ss.

George Popovec, Sr. Engr. IREX Corp. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) George Popovec

(Address) 1331 17th Street, Suite 800 Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 86

Deborah M. Dixon  
Notary Public

My Commission Expires: 8.10.89

RECEIVED  
STATE CORPORATION COMMISSION  
1-31-86  
JAN 31 1986  
1331-17th #800  
Denver, CO 80202  
Form CP-4  
Revised 08-84