

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-025-10076-0000

API NUMBER NA Comp. Date 10/57

LEASE NAME Theis

KCC CONSERVATION DIVISION  
130 S MARKET RM 2078  
WICHITA KS 67202-3802

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER J-3

1320 Ft. from S Section Line

3960 Ft. from E Section Line

LEASE OPERATOR Black Dome Energy Corporation

SEC. 22 TWP. 34 SRGE. 25 W (E) or (W)

ADDRESS 1536 Cole Blvd. Suite 325 Golden, Colo 80401 COUNTY Clark

PHONE# (303) 231-9059 OPERATORS LICENSE NO. 7142

Date Well Completed 10/57

Character of Well Gas

Plugging Commenced 3/27/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-30-95

The plugging proposal was approved on March 20, 1995 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Morrow Depth to Top 5620 Bottom T.D. 5860

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content     | From | To  | Size  | Put In | Pulled out |
|-----------|-------------|------|-----|-------|--------|------------|
| 5696-5712 | Gas & Water | 1214 | Sur | 8 5/8 | 1214   | NONE       |
|           |             | 5860 | Sur | 4 1/2 | 5860   | 3997.13    |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1) Sand back from 5790' to 5569' dump 4 sxs cement, 2) Pulled 123 jts. 4 1/2" csg. 3) Plug down 8 5/8" csg. w/ 300 # Hulls, 12 Gel, 50 sxs. 60/40 Pozmix 6% Gel, 8 Gel, 100 # Hulls, 150 sxs. 60/40 Pozmix 6% Gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. STATE CORP COMMISSION

Address Medicine Lodge, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Dome Energy Corporation

STATE OF Colorado COUNTY OF JEFFERSON, ss.

Black Dome Energy Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Huff, PRESIDENT

(Address) 1536 Cole Blvd. Ste 325, Golden, Co. 80401

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1995

My Commission Expires: August 28, 1998