

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-025-20-016-0000

LEASE NAME Klingen

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1450 Ft. from S Section Line

1450 Ft. from W Section Line

SEC. 14 TWP. 34 RGE. 25W (E) or (W)

COUNTY Clark

Date Well Completed 12-16-69

Plugging Commenced 4-6-95

Plugging Completed 4-10-95

LEASE OPERATOR Midco Exploration, Inc.

ADDRESS 414 Plaza Dr., Ste 204, Westmont, IL 60559

PHONE (316) 624-0156 OPERATORS LICENSE NO. 5254

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-6-95 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Chester Depth to Top _____ Bottom _____ T.D. 5835

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chester	gas & water	5641	5665	8 5/8	725	0
				4 1/2	5775	4545

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 20 sks. of cement & 200# hulls to 5400'

Pump 50 sks. of cement @ 750'

Pump 40 sks. of cement @ 400'

Put 10 sks. of cement from 40' to 0' Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6542 RECEIVED STATE CORPORATION COMMISSION

Address P.O. Box 506 Liberal, Kansas 67905-0506 MAY 01 1995

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Midco Exploration, Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill, agent

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Crown Consulting, Inc.

P. O. Box 1816, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 28th day of April, 19 95

My Commission Expires: _____

NOTARY PUBLIC, State of Kansas
Seward County
HELEN M. SMITH
My Appt. Exp. 3-3-97