

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22030-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 31-33S-38W  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: BANE TRUST B Well Number: 1-31  
County: STEVENS Total Vertical Depth: 6396 feet

Operator License No.: 5147  
Op Name: BEREDCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 6395 WITH 550 SX CMT  
Surface Casing Size: 8.625 feet: 1766 WITH 410 SX CMT

\$ 20787

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/03/2003 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GREG KLAUS Company: BEREDCO Phone: (316) 772-8650

Proposed Plugging Method: CIBP @ 5910' WITH 2 SX CMT. PLUG AT 1120' WITH 30 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/07/2003 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PERFS AT 5988-6005 & 6228-50'. DV TOOL @ 3178' WITH 250 SX CMT. TOC @ 1180'. SET CIBP @ 5910' WITH 2 SX CMT ON TOP. LOAD HOLE. SHUT DOWN OVER WEEKEND. 1ST PLUG LOAD HOLE WITH MUD & PUMP 30 SX CMT AT 1120'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 700'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 15 SX CMT TO SURFACE.

RECEIVED  
JUL 18 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1120' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

INVOICED

DATE

7-18-03

INV. NO.

2004060082

Form CP-2003