

To: 1 090782
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

3-7

API NUMBER 15- 189-22,096-0000
SW NE, SEC. 32, T. 33 S, R. 38 W/8
1980 feet from N8 section line
1980 feet from E section line
Lease Name Costley A Well # 2
County Stevens 208.00
Well Total Depth 6400 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1675

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS. 67905-0351

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: _____ Day: 5 Month: 3 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 6379' w/140 sx cement, PBSD 6310', Perfs at 6190-6208, 6218-24'
1st plug pump 2 sx hulls and 25 sx cement on bottom,
2nd plug at 1700' with 50 sx cement,
3rd plug at 650' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12 p.m. Day: 7 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 25 sx cement to bottom,
2nd plug at 2400-2300' with 30 sx cement,
3rd plug at 1700' with 50 sx cement,
4th plug at 650' with 40 sx cement,
5th plug at 40-0' with 10 sx cement.

3-10-97

KANSAS RECEIVED
CORP COMMISSION
MAR 10 P 3:50

Remarks: Used common cement by Sargent & Horton. Recovered 2428' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(XXX) (did not) observe this plugging.

DATE MAR 11 1997

Signed _____ (TECHNICIAN)

INV. NO. 47716

2-7 MAY 21 1997