

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22038-00-00
Spot: SESENW Sec/Twnshp/Rge: 31-33S-38W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: LIGHT F Well Number: 2
County: STEVENS Total Vertical Depth: 6403 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Conductor Pipe Size: 20 feet: 76 CIRCULATE
Production Casing Size: 5.5 feet: 6375 ETOC @ 5400
Surface Casing Size: 8.625 feet: 1742 CIRCULATE

3208.10

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/07/2003 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT FOR BOTTOM PLUG. LOAD HOLE WITH MUD. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 650' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/07/2003 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6220'. PERFS AT 5977-5981'. CIBP @ 6220'. PORT COLLAR @ 3095' WITH 60 SX CMT. PUMP 300# HULLS WITH 25 SX CMT. LOAD HOLE. 1ST PLUG PULL TO 1750'. LOAD HOLE & PUMP 50 SX CMT. DISPLACE WITH 37 BBL MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 650'. LOAD HOLE & PUMP 40 SX CMT. DISPLACE WITH 12 BBL MUD. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
MAR 24 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2230' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
MAR 20 2003
KCC Dodge City

Signed Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 3-25-03
REV. NO. 2003061333

Form CP-20