

1,00284

TO: STATE CORPORATION COMMISSION

3-25

API NUMBER 15-189-00475 SPUD DATE 11-53
C NE SEC. 34, T 33 S, R 38 W

0000

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BRECHEISEN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS 90.06

OPERATOR LICENSE # 5208

WELL TOTAL DEPTH 2771 FEET

OPERATOR: MOBIL OIL CORPORATION PRODUCTION CSG: SIZE 7" @ 2587' WITH 500 SX

NAME AND PO BOX 2173 SURFACE CASING: SIZE 10 1/2" @ 626' WITH 300 SX

ADDRESS LIBERAL, KS 67905-2173

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT AND HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 25 MONTH: 03 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT AND HORTON PLUGGING (PHONE) 580-854-6515

WERE: PERFS AT 2571-2864

1ST PLUG SET CIBP AT 1008' WITH 3 SX CEMENT ON TOP WELL SANDED UP TO 1100'- DRILLED 1953.

2ND PLUG SPOT 75 SX CEMENT AT 652'.

3RD PLUG SPOT 20 SX CEMENT FROM 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 25 MONTH: 03 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 1008' WITH 3 SX CEMENT ON TOP WELL SANDED UP TO 1100'- DRILLED 1953.

2ND PLUG SPOT 75 SX CEMENT AT 652'. GOOD CIRCULATION.

3RD PLUG SPOT 20 SX CEMENT FROM 40' TO 0'.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 683' OF 7" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

(I) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

INVOICED

DATE 4-2-99

INV. NO. 60772

RECEIVED
KANSAS CORP COM
APR 31 12 06

3-31-99