

1 060533

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20.318-0000

C NW NW, SEC. 6, T 33 S, R 40 W/8

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Log ^W "G" Well # 2

Operator: Anadarko Production Company

County Morton 176.80

Name & Address P. O. Box 351

Well Total Depth 5440 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1597 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:00 pm Day: 2 Month: April Year: 1985

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 5439' PRTD 5403' Perfs at 5319-5327'

1st plug pump 25 sx cement and 1/2 sack hulls to bottom

Pump cement through 4 1/2" casing with mud between plugs

2nd plug at 2618' with 50 sx cement 4th plug at 600' with 35 sx cement

solid bridge - hulls - plug

3rd plug at 1650' with 50 sx cement 5th plug at 40' -- cement to surface

with 10 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:00 pm Day: 2 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and 1/2 sack hulls to bottom, 2nd

plug at 2618' with 50 sx cement, 3rd plug at 1650' with 50 sx cement, 4th plug at 600'

with 35 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to sur-

face with 10 sx cement.

STATE CORPORATION COMMISSION

APR 12 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2618' 4 1/2" casing. Used Common sacked cement by Sargent's

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not) observe this plugging.

DATE 4-16-85

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 2739
4-2