

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21304-00-00  
Spot: SWNENE Sec/Twnshp/Rge: 6-33S-40W  
1250 feet from N Section Line, 1250 feet from E Section Line  
Lease/Unit Name: KREYA Well Number: 2H  
County: MORTON Total Vertical Depth: 2600 feet

Operator License No.: 4549 Conductor Pipe: Size feet: 84.50  
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 568  
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 2600  
HOUSTON, TX 77060 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/17/2002 12:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGIN Phone: (620) 697-2100

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. 1ST PLUG AT 1500' WITH 30 SX CMT. 2ND PLUG AT 600-0' WITH 70 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/17/2002 2:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2541'. PERFS AT 2305-2315'. PUMPED 200# HULLS WITH 25 SX CMT. 1ST PLUG PUMP 10 BBL MUD SPACER TO 1550'. PUMP 30 SX CMT. 2ND PLUG PUMP 15 1/2 BBL MUD SPACER TO 600'. CHECKED WITH WIRELINE. PUMP 65 SX CMT & PRESSURE TO 1000 PSIG. SHUT IN. BACKSIDE WAS CIRCULATED TO SURFACE. FLUID RAN OUT OF 2" CONNECTION ON 8 5/8".

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 25 2002

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Jim Holland PART II  
(TECHNICIAN)

INVOICED

JUN 24 2002

DATE

6-25-02

INV. NO.

2002062008