

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20218-00-01
Spot: NW SW Sec/Twnshp/Rge: 6-33S-40W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: SANTA FE TRAIL UNIT A Well Number: 1-2
County: MORTON Total Vertical Depth: 5440 feet

Operator License No.: 4549

Conductor Pipe: Size feet: 8 1/2 - 80

Op Name: ANADARKO PETROLEUM CORPORATION

Surface Casing: Size 8.625 feet: 1581 WITH 800 SX CMT

Address: 17001 NORTHCHASE DRIVE
HOUSTON, TX 77060

Production: Size 4.5 feet: 5440

Liner: Size feet:

Well Type: EOR

UIC Docket No: E23598.3

Date/Time to Plug: 05/14/2002 9:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Revd. from: DARREL SMITH

Company: ANADARKO PETROLEUM CORP.

Phone: (852) 601-3130

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT DOWN 2 3/8" TUBING TO PLUG BOTTOM. PERFORATE AT 1000'. PRESSURE UP TUBING. PUMP CMT DOWN BACKSIDE AND CIRCULATE.

Plugging Proposal Received By: STEVE DURRANT

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/14/2002 12:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5400'. PERFS AT 5346-5372'. 2 3/8" TUBING CEMENTED INSIDE 4 1/2" FROM 5300' - 0'. PUMP 200# HULLS & 25 SX CMT DOWN 2 3/8" TUBING TO PLUG BOTTOM. PERFORATE 2 3/8" TUBING & 4 1/2" CASING AT 1000'. RIG UP HALLIBURTON. PUMP 1/2 BBL WATER DOWN TUBING. PRESSURE TO 1250#. SHUT DOWN. CONNECT TO BACKSIDE, START PUMPING CMT. ESTABLISHED CIRCULATION THROUGH TUBING. PUMPED 230 SX CMT AT 350 PSIG. SHUT DOWN WITH BACKSIDE & TUBING FULL.

RECEIVED

JUN 17 2002

KCC WICHITA

Remarks: USED PREMIUM PLUS C CEMENT BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Jim Holland DIRTIE
(TECHNICIAN)

INVOICED JUN 12 2002

DATE

6-18-02

INV. NO.

2002061975

Form CP